

September 23, 2016

TO: All Bidders

RE: Informal Bid 2017-02 Addendum # 1

ADDENDUM NO. 1

This **ADDENDUM #1** forms part of Moore County's Informal Bid for Water Main Replacement - Seaboard St and South St for the County of Moore Public Works Department. All requirements of the original specifications remain in effect in their respective order. **Receipt of this Addendum must be acknowledged by its inclusion with the Informal Bid and noted as an inclusion on the sealed envelope.**

The following changes and/or clarifications are hereby made to the original Informal Bid:

NOTE: REVISED BID FORM ATTACHED

1. Question: Can you confirm with NCDEQ about making connections before final approval?
Answer: The connections cannot be made until after the line is tested and approved by MCPW. Please see the construction sequence in the Special Provisions.
2. Question: What do we do with the walls along South Street?
Answer: The proposed water main along these walls is a 2". It should be relatively easy to install the 2" water main around the walls and the installation route shall be determined in the field. Every precaution should be taken to not disturb the walls. The most southern walls shall not be disturbed at all.
3. Question: How do we abandon the existing water main?
Answer: The water main shall be capped at both ends. Flowable Fill is not needed.
4. Question: Will the 12" pipe supplied by the County have a warranty?
Answer: The vendor will not be responsible for pipe warranty supplied by the County but will be responsible for the installation.
5. Question: The construction sequence appears to call out tapping sleeves but the bid items show cut in tees.
Answer: Please use tapping sleeves.
6. Question: Is a plan holders list available?
Answer: A copy of the pre-bid sign in sheet is attached.
7. Question: Are we using SDR 21 PVC or should it have been C-900?
Answer: The plans call for the contractor supplied pipe (8", 6" and 2") to be SDC-21. The 12" pipe that Moore County is supplying is C-900. That is why there are two different materials on the plans.
8. Question: Item 4 on the bid sheet for South Street is blank.
Answer: Please refer to revised bid form attached.
9. Question: The asphalt patch quantity for Seaboard St looks extremely high on the bid sheet. Can you confirm if this quantity is correct or if the unit is in error? Also is this item for asphalt only and the ABC for the patch is paid under the gravel patch line items, or should this item include both 8" ABC and 2" asphalt shown on the detail?

Answer: The quantity and unit for the 6" x 2 Tapping Sleeve with 2" Gate Valve is "1-EA". The asphalt patching and gravel quantities and units have been revised for Seaboard St and South St on the attached Revised Bid Form. The Asphalt patch line item bid should include everything described in the specifications and shown on the detail. The Gravel lie item bid is for the gravel patching.

10. Question: What is the budget for this project?

Answer: Total budget for all projects within this budget is \$275,000. The County reserves the right to reject any and/or all bids. The County also reserves the right to award one project of this bid (Seaboard Street and/or South Street).

11. Question: When do you expect work to begin?

Answer: This project will require Board of Commissioner approval. Once a contract is executed a notice to proceed can be issued.

No further questions will be accepted. Sealed Bids are due to Terra Vuncannon at 206 South Ray Street Carthage NC 28327 by 4:00 pm Wednesday September 28, 2016. Opening will not be public.

END OF ADDENDUM NO. 1

Sincerely,

Terra Vuncannon
Purchasing Manager
County of Moore

**INFORMAL BID 2017-02 WATER MAIN REPLACEMENT - SEABOARD ST AND SOUTH ST
PRE-BID CONFERENCE
SEPTEMBER 22, 2018**

(please write all items legibly)

NAME (please print)	COMPANY	PHONE	E-MAIL
J. David Stike	Sanford Contractors, Inc.	919-775-7882	dstike@sanfordcontractors.com
Leon Hair	Utilities Plus Inc.	(910) 980-0946	utilitiesplusinc.com
Dor's Hair	" "	" "	" "
David Hilliard	Sandhill's Contractors	919-353-2078	jhilliard@sandhillscontractors.com
Logan Thomas	Thomas Construction Co.	919-352-8583	thomascnstruction@windstream.net
Tommy Strickland	Columbus Utilities Inc.	710-649-7133	columbusutilities@earthlink.net
Scott Hedrick	Triple T Plumbing & Utilities Inc.	(836) 695-1090	SCOTTHEDRICK@TRIADPIPE.COM
Jeff Williams	B. R. S., Inc.	(704) 463-1355	brs@brsinc.net
Randy Gould	MC DADD	(910) 747-4300	mcadd@mcaddinc.com
Marshall McBryde	MC PWD	919-4308	mcbride@mcbride.com

**SEABOARD STREET AND SOUTH STREET WATER MAIN REPLACEMENT
TO SERVE
MOORE COUNTY PUBLIC WORKS DEPARTMENT**

REVISED BID FORM

This Bid consist of equipment, labor, materials, and traffic control for the **Seaboard Street and South Street Water Main Replacement** project. Use this form for submitting Bids. No alterations, changes in Bid format will be allowed. All items should be priced for the units and quantities specified. The County of Moore shall reserve the right to reject any or all Bids. Opening will not be public.

SEABOARD STREET WATER MAIN REPLACEMENT					
	Item Description	Quantity	Unit	Unit Cost	Total Cost
1	Mobilization	1	LS		
2	12" C900 PVC Water Main (Installation Only) (Sta. 9+99 to Sta. 26+75)	1,640	LF		
3	12" DIP Water Main (Sta. 9+99 to Sta. 26+75)	40	LF		
4	8" SDR21 PVC Water Main (Sta. 0+00 to Sta. 9+99)	960	LF		
5	8" DIP Water Main	40	LF		
6	Cut in Tee for Water Main Connection (Sta. 0+00) 1 - 6" x 6" Tee 1 - 8" x 6" Reducer 1 - 6" Gate Valve	1	EA		
7	Hydrant Leg Connection (Sta. 0+20 and Sta. 3+90) 1 - 8" x 6" Tee 1 - 6" Gate Valve 20 LF - 6" DIP Pipe	2	EA		
8	Fire Line Connection (Sta. 3+61) 1 - 8" x 6" Tee 1 - 6" Gate Valve 20 LF - 6" DIP Pipe	1	EA		
9	Standard 1" Water Service Connection Renewed	6	EA		
10	2" Water Service Connection (Sta. 3+51 and Sta. 7+45)	2	EA		
11	8" Water Main Connection (Sta. 8+16) 1 - 8" x 8" Tee 1 - 8" Gate Valve 20 LF - 6" DIP Pipe	1	EA		

12	Hydrant Leg Connection (Sta. 12+33, Sta. 17+04 and Sta. 21+82) 1 - 12" x 6" Tee 1 - 12" Gate Valve 1 - 6" Gate Valve 20 LF - 6" DIP Pipe	3	EA		
13	6" Water Main Connection (Sta. 19+98) 1 - 12" x 6" Tee 1 - 6" Gate Valve 10 LF - 6" DIP Pipe	1	EA		
14	Cut in Tee for Water Main Connection and Hydrant Leg Connection (Sta. 26+75) 1 - 8" x 8" Tee 1 - 8" Coupling 1 - 8" 90 Degree Bend 1 - 8" Gate Valve 1 - 8" x 6" Tee 1 - 12" x 8" Reducer	1	EA		
15	8" Plug to Abandon Existing Water Main (Sta. 0+00 and Sta. 26+75)	2	EA		
16	8" x 6" Reducer (Sta. 0+00)	1	EA		
17	12" x 8" Reducer (Sta. 9+99)	1	EA		
18	6" Mega Lug/Grip Ring	34	EA		
19	8" Mega Lug/Grip Ring	14	EA		
20	12" Mega Lug/Grip Ring	18	EA		
21	Valve Marker	8	EA		
22	Valve Box and Concrete Ring	13	EA		
23	Temporary Check Dam	1	EA		
24	Temporary Silt Fence	2,000	LF		
25	Seeding & Mulching	0.50	AC		
26	Gravel Patch with ABC Stone	20	SY		
27	Asphalt Patch with 9.5B Asphalt	110	SY		
TOTAL BID PRICE – SEABOARD STREET					

SOUTH STREET WATER MAIN REPLACEMENT

	Item Description	Quantity	Unit	Unit Cost	Extended Cost
1	Mobilization	1	LS		
2	6" SDR21 PVC Water Main	480	LF		
3	2" SDR21 PVC Water Main	1,960	LF		
4	6" x 2" Tapping Sleeve with 2" Gate Valve	1	EA		
5	6" Water Main Connection (Sta. 3+28 and Sta. 7+52) 1 - 2" x 2" Tee 1 - 6" x 2" Tapping Saddle 1 - 2" Gate Valve 1 - 2" 90 Degree Bend	2	EA		
6	6" Water Main Connection (Sta. 19+50) 1 - 6" x 6" Tee 1 - 6" Gate Valve 1 - 6" x 2" Reducer 1 - 6" Coupling 200 LF of 6" SDR21 PVC Water Main	1	EA		
7	Standard 1" Water Service Connection	5	EA		
8	Cut in Tee for Water Main Connection (Sta. 24+25) 1 - 6" x 6" Tee 1 - 6" Gate Valve 1 - 6" Coupling	1	EA		
9	Hydrant Relocation (Sta. 19+50 and Sta. 24+00)	2	EA		
10	6" Plug to Abandon Existing Water Main (Sta. 19+50 and Sta. 24+25)	2	EA		
11	2" Gate Valve	1	EA		
12	6" 90 Degree Bend	1	EA		
13	6" 22 Degree Bend	1	EA		
14	2" Mega Lug/Grip Ring	17	EA		
15	6" Mega Lug/Grip Ring	29	EA		
16	Valve Marker	6	EA		
17	Valve Box and Concrete Ring	6	EA		
18	Seeding & Mulching	0.50	AC		
19	Gravel Patch with ABC Stone	8	SY		
20	Asphalt Patch with 9.5B Asphalt	21	SY		
TOTAL BID PRICE – SOUTH STREET					

Responsive Bid must include the following documents:

- 1. Signed Bid Form**
- 2. Notarized Non-Collusion Affidavit**
- 3. Notarized E-Verify Affidavit**
- 4. Current W-9 Form**
- 5. Vendor Application (including references, equipment and resumes)**
- 6. Copy of all pertinent licenses**
- 7. Proof of Insurance**

On behalf of _____ (Bidder), I am submitting a bid for the **Seaboard Street and South Street Water Main Replacement** project. This Bid covers equipment, labor, materials, traffic control and all other incidentals to complete the project. I certify that the contents of this Bid are known to no one outside the undersigned, and to the best of my knowledge all requirements have been complied with.

By: _____
(Printed)

By: _____
(Signature)

Date: _____

Receipt of the following addendum is acknowledged:

Addendum No. _____ Received: (circle) YES / NO Date: _____

Addendum No. _____ Received: (circle) YES / NO Date: _____

Addendum No. _____ Received: (circle) YES / NO Date: _____