

October 21, 2016

TO: All Bidders

RE: Informal Bid 2017-03 Addendum # 2

ADDENDUM NO. 2

This **ADDENDUM #2** forms part of Moore County's Informal Bid for the WPCP Gravity Sewer Main and Flume Upgrade for the County of Moore Public Works Department. All requirements of the original specifications remain in effect in their respective order. **Receipt of this Addendum must be acknowledged by its inclusion with the Informal Bid and noted as an inclusion on the sealed envelope.**

The following changes and/or clarifications are hereby made to the original Informal Bid:

NOTE: THE COUNTY IS REVISING THE SCOPE, DRAWINGS AND BID TAB FOR THIS PROJECT. PLEASE NOTE THE BID OPENING DATE HAS BEEN POSTPONED UNTIL REVISIONS ARE COMPLETED.

Below are responses to questions received prior to pre-bid. Construction details and flume plan and profile drawings are attached to this addendum.

1. Question: Is there an estimated cost or budget available?
Answer: The budget for this project is \$150,000.
2. Question: Are there any union requirements for this project/
Answer: No.
3. Question: Is a plan holders list available?
Answer: A copy of the sign-in sheet from the mandatory pre-bid is included in this addendum.
4. Question: The plan calls for the pipe to be 18" DIP and the bid schedule calls for it to be 18" PVC. Which one is correct?
Answer: DIP pipe for areas over 12' and PVC for areas under 12'.
5. Question: Will the plant be shut down or will the Contractor be required to bypass the sewer flow?
Answer: The plant will not be shut down and the Contractor will be required to bypass the sewer flow.
6. Question: Which way do the electrical lines go from the large transformers and small electrical box adjacent to the sewer main?
Answer: Electrical plans will be included when the revised plans are issued.
7. Question: Is the contractor to fill in dirt behind the block wall?
Answer: No. Moore County will be responsible for the retaining wall fill. Revised drawings will show wall dimensions and block details.

8. Question: Both bypass pumping operations plan describe have flow discharging into the influent control box. Is this the same control box that is shown to have new 18” PVC suction and discharge piping? If so please provide a bypass plan to do the work in the control box
Answer: The plumbing of the control box for the drop and suction lines will need to be coordinated with the WPCP staff. The by-pass pumping that will be used for the sewer main installation can be shut down for a few hours to do this work. The inflow to the control box from the collection system cannot be by-passed. Again, you will need coordinated with the WPCP staff to work during low inflow times.
9. Question: Is a bid bond required/
Answer: No

END OF ADDENDUM NO. 2

Terra Vuncannon
Purchasing Manager
County of Moore

INFORMAL BID 2017-03 WPCP GRAVITY SEWER MAIN AND FLUME UPGRADE
 PRE-BID CONFERENCE
 OCTOBER 20, 2016

(please write all items legibly)	NAME (please print)	COMPANY	PHONE	E-MAIL
	Willis Harper	Frank Home Construction, Inc	910-649-7803	hcf40@kshop.com
	Leonard McBoyle	M.C. P&V	910-847-6315	lmcboyle@moorecountync.gov
	Janna Naji	MC WPCP	910-281-3146	jnaji@moorecountync.gov
	Randy Gault	M.C. P&V	947-4300	rgault@moorecountync.gov
	Carrod Hilliard	Sandhills Contractors	919-353-2078	jhilliard@sandhillscontractors.com
	Steve Williamson	SKC znc.	336-873-9999	skc.znc@emby.mil.com
	B. MUSSO	T.A. LOVING CO	919- 888 -8400	bmusso@taloving.com
	Audrey Strickland	Columbus Utilities	910-649-7133	astri@businessutilitiesinc.com
	Rex Downs	Morrison	910-281-3144	rdowns@moorecountync.gov
	David Laurita	" "	" "	dlaurita@moorecountync.gov
	Rip Collins	ELS Inc	910-347-9010	rcollins@elsinc.tulsa.ok.us